

**Appendix 21-12 (R)**  
**Broward County Project Trip Assignment**

**Revised October 2008**

**Project Assignment to Miramar Parkway Ramps**  
*Beacon Countyline DRI*

Movement	Existing (2007) Conditions		NB Project Volume	% Outbound Assignment	% Inbound Assignment	SB Project Volume
	Volume	% of Mainline				
Mainline NB Volume	7,527	---	329	13.2%	13.2%	147
NB I-75 to EB Miramar Off-Ramp Volume	952	12.6%		1.7%	---	---
SB I-75 from Miramar On-Ramp from the east	---	---	---	---	1.7%	19
NB I-75 to WB Miramar Off-Ramp Volume	1,596	21.2%		2.8%	---	---
SB I-75 from Miramar On-Ramp from the west	---	---	---	---	2.8%	31
			Outbound Project Volume:	2,494	Inbound Project Volume:	1,111

Highlighted cells were Revised October, 2008